



260 Cranberry Highway
 Orleans, MA 02653
 508.255.6511 P 508.255.6700 F
 Orleans | Sandwich | Nantucket
 coastalengineeringcompany.com

TRANSMITTAL

To: Provincetown Conservation Commission
 Attn: Tim Famulare, Agent
 260 Commercial Street
 Provincetown, MA 02657

Date: 7/11/18 **Project No.** C14394.08
Via: 1st Class Mail Pick up Delivery Fed Ex
Phone:
Fax:

Subject: Notice of Intent Application Filing Package
 Proposed Funicular & Site Improvements
 Cape Cod Pilgrim Memorial Association
 1 High Pole Hill Road
 Provincetown, MA
 Map 12-1 Parcel 27

No. of pages to follow:

Plans Copy of Letter Specifications Other

We are sending the following items:

Copies	Date	No.	Description
10	Rev. 7/9/18		Hawk Design, Bradford Access Project
10	Rev. 7/9/18		Coastal Engineering Co., Inc., Plan Showing Proposed Site Improvements

These are transmitted as checked below:

for approval for your use as requested for review & comment


Remarks: Enclosed please find copies of the attached plans for the referenced project.

If you have any questions, please contact our office.

cc: Mass. DEP/SERO - Wetlands
 Cape Cod Pilgrim Memorial Association
 John A. Bologna, Project Manager
 Jason R. Norton, Project Manager


By: Jay Norton

D:\DOC\C14300\14394.08\Permitting\NOI\Revised Plan Submittal #2\Transmittal Template.doc



PLANT SCHEDULE SITE

TREES	QTY	BOTANICAL NAME	COMMON NAME	CONT	CAL	PLANT SIZE	NATIVE ALTERNATIVE
AR-OG	2	Acer rubrum 'October Glory'	October Glory Maple	B & B	3-3.5" CAL.		
EVERGREEN TREES	QTY	BOTANICAL NAME	COMMON NAME	CONT.	CAL.	PLANT SIZE	
PGB	3	Picea glauca	White Spruce	B & B		8-10' HT.	Juniperus virginiana 'Idlywild'
FLOWERING TREES	QTY	BOTANICAL NAME	COMMON NAME	CONT.	CAL.	PLANT SIZE	
CF-CP	4	Cornus florida 'Cherokee Princess'	Cherokee Princess Dogwood	B & B	3-3.5" CAL.		
SHRUBS	QTY	BOTANICAL NAME	COMMON NAME	CONT.	CAL.	SIZE	
AC-G	4	Amelanchier canadensis 'Glennform'	Rainbow Pillar Serviceberry	B & B		6-8' HT.	
DG-N	24	Deutzia gracilis 'Nikko'	Slender Deutzia	Cont.		15-18" SPD.	Potentilla fruticosa
HM-CR	65	Hydrangea macrophylla 'Cityline Rio'	Cityline Rio Hydrangea	Cont.		15-18" HT.	
HS-A	13	Hibiscus syriacus 'Aphrodite'	Aphrodite Rose of Sharon	B & B		5-6' HT.	Clethra alnifolia
HY-Q	12	Hydrangea quercifolia	Oakleaf Hydrangea	B & B		2-2.5' HT.	
IC-ST	16	Ilex crenata 'Soft Touch'	Soft Touch Japanese Holly	Cont.		18-24" HT.	Ilex glabra
IM-BP	23	Ilex x meservae 'Blue Princess' Shrubform	Blue Princess Holly Shrubform	B & B		3.5-4' HT.	
MP	7	Myrica pensylvanica	Northern Bayberry	B & B		3-3.5' HT.	
R-CW	3	Rhododendron 'Cunningham's White'	Cunningham White Rhododendron	B & B		3-3.5' HT.	
TM-H	34	Taxus x media 'Hicksii'	Hicks Yew	B & B		4-5' HT.	
TO-EG	15	Thuja occidentalis 'Emerald Green'	Emerald Green Arborvitae	B & B		8-10' HT.	Juniperus virginiana 'Idlywild'
GROUND COVERS	QTY	BOTANICAL NAME	COMMON NAME	CONT.		SPACING	
P	83	Perennials	Assorted Perennials	1 gal		18" o.c.	Echinacea purpurea, Rudbeckia, Tiarella, Coreopsis rosea, Asclepias tuberosa
RO-AD	18	Rosa x 'Apricot Drift'	Apricot Drift Rose	1 gal		24" o.c.	



*NOTE:
REFER TO SAFE HARBOR ENVIRONMENTAL
"FUNICULAR SLOPE ENVIRONMENTAL
MANAGEMENT PLAN" FOR SLOPE RESTORATION
AND PLANTING

*NOTE:
ALL DISTURBED GROUND PLANE TO
BE PLANTED WITH NEW ENGLAND
CONSERVATION/ WILDLIFE MIX OR
EQUAL. SEE NOTE BELOW.

*NOTE:
REFER TO SAFE HARBOR ENVIRONMENTAL
"FUNICULAR SLOPE ENVIRONMENTAL
MANAGEMENT PLAN" FOR SLOPE RESTORATION
AND PLANTING

CONSERVATION NOTES

- ALL WORK TO BE DONE IN ACCORDANCE WITH THE DEP ORDER OF CONDITIONS IN ADDITION TO ALL LOCAL ORDINANCES.
- NO HERBICIDES OR PESTICIDES SHALL BE USED ON SUBJECT PROPERTY.
- THE LIMIT OF WORK LINE SHALL BE PERMANENTLY MARKED AFTER REMOVAL OF THE HAYBALE LINE OR OTHER APPROVED S.E.C. METHODS.
- A BUFFER ZONE OF NATURAL VEGETATION SHALL BE LEFT UNDISTURBED OUTSIDE THE WORK LIMIT AREA.
- ALL EXPOSED SOILS TO BE LOAMED AND SEEDED.
- LANDSCAPE CONTRACTOR SHALL MEET WITH CONSERVATION AGENT PRIOR TO COMMENCEMENT OF ANY WORK.
- A TEMPORARY AUTOMATED ABOVE-GROUND IRRIGATION SYSTEM MAY BE REQUIRED FOR THE FIRST TWO-THREE GROWING SEASONS (AFTER WHICH THE SYSTEM IS TO BE REMOVED).

New England Conservation/Wildlife Mix

SPECIES: Virginia Wild Rice, (Elymus virginicus), Little Bluestem, (Schizachyrium scoparium), Big Bluestem, (Andropogon gerardii), Creeping Red Fescue, (Festuca rubra), Switch Grass, (Panicum virgatum), Partridge Pea, (Chamaecrista fasciculata), Deer Tongue, (Panicum clandestinum), Indian Grass, (Sorghastrum nutans), Ox Eye Sunflower, (Helipopsis helianthoides), Common Milkweed, (Asclepias syriaca), Spotted Joe Pye Weed, (Eupatorium maculatum), Grass Leaved Goldenrod, (Euthamia graminifolia), Blue Vervain, (Verbena hastata), New England Aster, (Aster novae-angliae), Early Goldenrod, (Solidago juncea).
Source: New England Wetland Plants.



Hawk Design, Inc.
Landscape Architecture
Land Planning
Sagamore, MA
508-833-8800
info@hawkdesigninc.com

HAWK DESIGN, INC. 2018
THIS DRAWING AND ALL INFORMATION CONTAINED
HEREIN IS PROPRIETARY INFORMATION OF HAWK
DESIGN, INC. AND MAY NOT BE COPIED OR
REPRODUCED, EITHER IN WHOLE OR IN PART, BY
ANY METHOD, WITHOUT WRITTEN PERMISSION OF
HAWK DESIGN, INC.

BROWN LINDQUIST FENUCCIO & RABER
ARCHITECTS, INC.
200 WILLOW STREET, SUITE A
YARMOUTHPORT, MA 01986
PH: 508-882-8800
FAX: 508-882-2688

COASTAL
ENGINEERING
COMPANY, INC.
100 STATE ST. 10TH FLOOR
PROVINCETOWN, MA 01970



Date: 04.20.18

Revisions:
Num. Date Description
1. 06.07.18 Revised Plan
2. 07.09.18 Revised Plan



Bradford Access Project
Provincetown, Massachusetts

Drawn By: J.P. Checked By: O.H.

Submission
Planting
Plan

Scale: 1/4" = 1'-0"

Sheet:
L1

Base plan information provided electronically
by Coastal Engineering Company of Orleans,
Massachusetts and Brown Lindquist Fenuccio
& Raber Architects, Inc. of Yarmouthport, MA.



260 Cranberry Highway
 Orleans, MA 02653
 508.255.6511 P 508.255.6700 F
 Orleans | Sandwich | Nantucket
 coastalengineeringcompany.com


TRANSMITTAL

To: Provincetown Conservation Commission
 Attn: Tim Famulare, Agent
 260 Commercial Street
 Provincetown, MA 02657

Date: 7/12/18 **Project No.** C14394.08
Via: 1st Class Mail Pick up Delivery Fed Ex
Phone:
Fax:

Subject: Notice of Intent Application Filing Package
 Proposed Funicular & Site Improvements
 Cape Cod Pilgrim Memorial Association
 1 High Pole Hill Road
 Provincetown, MA
 Map 12-1 Parcel 27

No. of pages to follow:



Plans Copy of Letter Specifications Other

We are sending the following items:

Copies	Date	No.	Description
10	7/12/18		Funicular Construction Methodology

These are transmitted as checked below:

for approval for your use as requested for review & comment

Remarks: Enclosed please find copies of the attached documents for the referenced project.

If you have any questions, please contact our office.

cc: Mass. DEP/SERO - Wetlands
 Cape Cod Pilgrim Memorial Association
 John A. Bologna, Project Manager
 Jason R. Norton, Project Manager

By: Jay Norton

D:\DOC\C14300\14394.08\Permitting\NOI\Revised Plan Submittal #2\Transmittal Template2.doc



July 12, 2018

Project # C14394.08

Conservation Commission
Attn: Tim Famulare, Agent
260 Commercial Street
Provincetown, MA 02657

By Hand Delivery

Re: Funicular Construction Methodology
Proposed Funicular & Site Improvements
Cape Cod Pilgrim Memorial Association
1 High Pole Hill Road
Provincetown, MA
Map 12-1 Parcel 27

On behalf of our client, Cape Cod Pilgrim Memorial Association, this letter is intended to provide general information regarding the construction methodology of the Funicular project. It has been broken down into 6 categories as follows: Mobilization and Site Preparation, Support Foundation System, Funicular Construction, Pavilion Construction, Landscaping and Hardscaping, and Operations and Commissioning.

Mobilization and Site Preparation (Duration: Approximately 1-2 Weeks)

At the commencement of construction, the contractor will mobilize equipment to the site including but not limited to: crane, excavator, pick-up trucks with equipment and tools. The crane will be positioned at either the top of the hill or the bottom of the hill depending on contractor preference. The contractor will also initiate limits of work fencing to demarcate the construction zone.

The site will be prepared as shown on the design plans, with the majority of the clearing to be conducted by hand. The slope is too steep for machines, so a crane might be used to supplement areas that cannot be achieved by foot.



Figure 1 - Typical Crane

Erosion control measures as consistent with Safe Harbor Environmental protocols will be implemented immediately following site preparation to aid in stabilization and the control of runoff.



Figure 2 - Helical Anchor

Support Foundation System (Duration: Approximately 4 weeks)

Upon completion of the site preparation, the contractor shall install the low impact support foundation system that consists of helical anchors. The helical anchors are mechanically torqued into the ground to alleviate vibratory forces to the substrate and surrounding areas. The helical anchors are embedded into the substrate to a depth of approximately 30'. There are approximately 2 helical piers per every 10 feet. This is achieved by either crane, or by hand torque equipment. Once the anchors have reached their required embedment depth, the contractor shall prepare the connection system to accept the funicular track and associated bracket supports. You can see from Figure 3 the ground surrounding the funicular and helical anchor system is very much intact.



Figure 3 - Similar installation

Funicular Construction (Duration: Approximately 4 weeks)




Figure 4 - Laying the track system

After the support foundation is complete, the contractor shall commence on the installation of the elevator pit and machine room areas at the top and bottom of the funicular system. The tension weight frame is then placed in the machine room prior to the installation of the track system.

The track system and associated emergency access stairway is then installed with a crane starting from the bottom and working their way to the top of the funicular system. Once the track is installed, the cable system is constructed and the cab is then attached to the track and cable system.

Pavilion Construction (Duration: Approximately 4 weeks)

Following the installation of the funicular system, the associated pavilion structure shall be constructed at the base of the system as well as the platform system at the top of the funicular. In parallel with this phase, the electrical and mechanical components of the funicular system will be finalized.

Landscaping, Lighting, Hardscaping and Drainage (Duration: Approximately 3 Weeks)

This phase can occur in conjunction with the pavilion structure phase as long as there are no site conflicts. The drainage system is to be installed first, with the hardscaping, landscaping and lighting to follow in accordance with the design plans.

Operations/Commissioning of System (Duration: Approximately 1-2 Weeks)

Lastly, the operation component shall be finalized including kiosk implementation and associated operational components. The commissioning of the system is required to ensure proper functionality and safety.

Furthermore, as specifically stated in Safe Harbor's Long-Term Funicular Slope Management Plan, the site will be inspected daily during construction. This document has also been submitted as part of the supplemental information for the commission. If you have any questions or require additional information, please give our office a call. Thank you.

Sincerely,

COASTAL ENGINEERING CO., INC.



Jay R. Norton
Senior Project Manager

Enclosures: as stated

cc: Mass. DEP/SERO - Wetlands
Cape Cod Pilgrim Memorial Association
John A. Bologna, Project Manager

SAFE HARBOR

ENVIRONMENTAL MANAGEMENT
HABITAT RESTORATION



Date: July 9, 2018

To: Provincetown Conservation Commission

From: Safe Harbor Environmental Services

**Contact: PO Box 275, Provincetown MA gordonpeabody@gmail.com
phone 508-237-3724**

Re: Pilgrim Monument and Provincetown Museum

REVISED: FUNICULAR SLOPE ENVIRONMENTAL MANAGEMENT PLAN

I. Slope Characteristics and Condition

1. Provincetown consists entirely of **Post Glacial, unconsolidated** sediments. These materials have settled and gravity compacted, during the past 2,000 years, most having a slender profile of overburden. These materials exhibit exceptional percolation properties.
2. This particular dune was among the first created in Provincetown, as the stable, Harbor shoreline (Dynamic Equilibrium, Graham Geise) allowed the landform to expand to the north. Abundant sand supply was delivered from the then Ocean beach, which is where the current Church Cemetery is now.
3. Now that this historic landform is no longer collecting sand or eroding to nourish the Ocean beach, it is no longer performing as a dune and cannot qualify for protection as such (Graham Geise CCS; Jim Mahala DEP)
4. Similar to parallel landforms along Bradford Street, this landform is stable.

II. Excavation protocol

1. Helical anchors shall be used to avoid excavation

III. Concrete protocol

1. To protect slope ground water from high pH concrete percolate, poly liners shall be used beneath forms and to collect over pour.
2. Concrete shall be managed per Safe Harbor guidelines "*Managing Concrete in Sensitive Areas*" Safe Harbor 2018, 6 pages.


IV. Erosion Control

1. Raw areas shall be stabilized with jute netting secured by cornstarch ground staples.
2. Multiple lines of minimal, horizontal benching shall be created to manage and recharge storm water.
3. Zero discharge performance standards shall be maintained with integrated biog-silt fence erosion control systems, as described in, "***Biog-Silt fence Erosion Control System***", Safe Harbor 2017 (7 pages).
4. A semi-permeable filter fabric shall be used as a silt fence.
5. The filter fabric shall be properly pressed (not dug) into the grade 4-6 in. using a lawn-edging tool.
6. The filter fabric shall be vertically stapled to additional Oak stakes inserted every 5 ft.
7. Low impact jute netting/straw bioglogs shall be installed on the activity-area-side of the silt fence.
8. Bioglogs shall be 12-16 in. in diameter, as required to maintain zero discharge performance standards.
9. The bioglogs shall be secured with 6 in. cornstarch ground staples, every ft.
10. Anytime sediment buildup against the bioglog exceeds 4 in. the load shall be removed by hand, to a location outside the LOW.
11. These erosion control systems shall be regularly inspected
12. This system shall be inspected weekly and following storm pulse events and serviced to maintain performance standards.
13. Where EC systems intersect site access areas, necessary openings shall be reclosed at end of day.

V. Slope Restoration

1. No changes to native species are proposed for the slope.
2. Invasive vegetation shall be removed using Safe Harbor protocols for working with invasive vegetation. Protocols are described in "***The Dirty Dozen of Cape Cod, Third edition***" Safe Harbor, 2017 (20 pages).
3. Specific, low impact protocols are modeled after successful, exceptionally steep Safe Harbor slope stabilization projects. (***see images below***)
4. Stabilization and revegetation are ongoing, linked projects
5. Slopes shall be stabilized using Safe Harbor natural systems, as described in Safe Harbor Booklet "***Stabilizing Steep and Very Steep Slopes Using Natural Systems***" Safe Harbor, 2017 (15 pages).
6. Native plantings will be supervised by Safe Harbor, using established, Safe Harbor protocols.
7. End of growing season report shall be provided to the Commission.

VI. Slope Restoration Model : Images by G. Peabody, over 5 month period



VII. Funicular Slope Planting Plan

1. Native vegetation on slope removal area will be transplanted on adjacent slope when feasible.
2. Transplanting shall be performed by trained Safe Harbor workers.
3. All vegetation removal work shall be done by hand.
4. Trees shall be removed by professional arborist
5. Tree removal may require crane assist.
6. A portion of removed trees may be left on adjacent slope as habitat.
7. Removed trees dbh > 12" will be replaced 3-1, same species, 7 ft tall, and 3- 1 gal native Bear oaks
8. Removed trees dbh 12"-6" will be replaced 2-1, same species, 7 ft tall, and 3- 1 gal native Bear oaks.
9. Removed trees dbh 6"-4" will be replaced 1-1, same species, 7 ft tall and 3- 1 gal native Bear oaks.
10. Trees will be sited in open areas and installed a minimum of 10' away from any funicular components to avoid any future conflicts.
11. Tree replacement plantings shall be performed by trained Safe Harbor workers.
12. Invasive vegetation shall be removed from the Funicular slope area by trained Safe Harbor workers in areas immediate to the funicular structure.
13. Remaining bare areas beneath Funicular shall be seeded with native grasses.
14. Additional areas on adjacent slopes, equal to the total square footage of slope disturbance, shall be seeded with native shade grass seed mix.
15. Limited, seasonal above ground irrigation, shall be incorporated as necessary, to protect survivability.

VIII. LONG RANGE FUNICULAR SLOPE MANAGEMENT PLAN (5 YRS)

1. **GOALS:** The goal of this plan is to establish long term monitoring protocols to protect the performance standards of the funicular area slope.
2. **PERFORMANCE STANDARDS:** Maintaining effective stability; erosion control; storm water management; water quality; and habitat restoration.
3. **STRATEGIES:** Our core strategy is based on using natural systems, utilizing native vegetation and existing profiles, creating minimal disturbance.
4. **INSPECTIONS: Short Term:** During construction-daily; First growing season-weekly; Off season: monthly; and post Pulse event.
5. **INSPECTIONS: Long Term:** Second growing season-biweekly; Therein after-monthly; and post Pulse event.
6. **REPORTS:** Written, photo documented reports shall be filed with the Commission: project updates during construction; planting activity reports.
Annually for 5 years: end of growing season report; end of year report assessing the performance of individual and integrated natural systems in maintaining project goals.